

S.C. TIAB S.A. Agentia TIAB Industrie Ploiesti	JURNAL DE CABLURI 6kV	PT.1972-34-E.8-01 Faza: Caiet de sarcini REV. 0 PAG.1 DIN 2 DATA: 01.2020
	INSTALATII ELECTRICE MEDIE TENSIUNE	

COMANDA NR :	Sef proiect : Stefan D.
BENEFICIAR : AMBRO S.A.	Proiectat : Dirvaru G.
INSTALATIA : MODERNIZARE STATIE ELECTRICA DE CONEXIUNI 6kV	Intocmit : Dirvaru G.

Nr crt	Marca	Tip cablu si sectiune [mm ²]	U _N [kV]	Pleaca de la	Soseste la	Lungime [m]
1.		5 x (3 x A2XSY 1x400)	3,6/6	Statia electrica 110/6kV EON / Celula	Statia electrica 6kV AMBRO / Celula CB_A_10 – Sectia A	
2.		3 x (3 x A2XSY 1x185)	3,6/6	Celula CB_A_9	Generator	
3.		4 x (3 x A2XSY 1x150)	3,6/6	Celula CB_A_2	Platforma mansonare cabluri Statia 21 – Feeder 1	
4.		4 x (3 x A2XSY 1x150)	3,6/6	Celula CB_A_3	Platforma mansonare cabluri Statia 21 – Feeder 2	
5.						
6.		4 x (3 x A2XSY 1x150)	3,6/6	Celula CB_A_5	Platforma mansonare cabluri Statia 28 – Feeder 1	
7.		4 x (3 x A2XSY 1x150)	3,6/6	Celula CB_A6	Platforma mansonare cabluri Statia 28 – Feeder 2	
8.						
9.		2 x (3 x A2XSY 1x240)		Celula CB_A_11	Baterie condensatoare CAP1	
10.		3 x A2XSY 1x150		Celula CB_A_8	Trafo TSI_A	
11.		5 x (3 x A2XSY 1x400)	3,6/6	Statia electrica 110/6kV EON / Celula	Statia electrica 6kV AMBRO / Celula CB_B_10 – Sectia B	
12.		4 x (3 x A2XSY 1x150)	3,6/6	Celula CB_B_6	Platforma mansonare cabluri Statia 21 – Feeder 3	
13.		4 x (3 x A2XSY 1x150)	3,6/6	Celula CB_B_7	Platforma mansonare cabluri Statia 28 – Feeder 3	
14.		2 x (3 x A2XSY 1x240)		Celula CB_B_11	Baterie condensatoare CAP2	
15.		3 x A2XSY 1x150		Celula CB_B_8	Trafo TSI_B	
16.		3 x A2XSY 1x150		Celula CB_B_2	Platforma mansonare cabluri Trafo T1 Carton Ondulat	

S.C. TIAB S.A. Agentia TIAB Industrie Ploiesti	JURNAL DE CABLURI 6kV	PT.1972-34-E.8-01 Faza: Caiet de sarcini REV. 0 PAG.2 DIN 2 DATA: 01.2020
	INSTALATII ELECTRICE MEDIE TENSIUNE	

Nr crt	Marca	Tip cablu si sectiune [mm ²]	U _N [kV]	Pleaca de la	Soseste la	Lungime [m]
17.		3 x A2XSY 1x150		Celula CB_B_3	Platforma mansonare cabluri Trafo T2 Carton Ondulat	
18.		3 x A2XSY 1x150		Celula CB_B_4	Statie 6kV Treapta 1 – mansonare cu cablu existent	
19.		3 x A2XSY 1x150		Celula CB_B_5	Plecare TR1 Treapta 1 – mansonare cu cablu existent	
20.						
21.						
22.						